

# TENTATIVE TIMELINE\*

The Project is planned to be divided into three main phases of operation in order to reduce community impact.

## NOTICE OF PREPARATION (NOP)

Notice of Preparation (NOP) prepared to seek input from local agencies and the public regarding the scope and content of the environmental information to be included in the Draft Program Environmental Impact Report (PEIR)

2023



FALL  
2024



## DRAFT PROGRAM ENVIRONMENTAL IMPACT REPORT

1. Draft PEIR written
2. Public and agency review of Draft PEIR (min. 45 days review period)
3. Final PEIR prepared with inclusion of responses to public comments


## BOARD OF SUPERVISORS REVIEW

1. Project Approval Recommendation Process begins
2. Final PEIR and Project Approval under consideration by Board of Supervisors

SPRING  
2025



LATE  
2025



## PHASE 1: SITE PREPARATION / CONSTRUCTION BEGINS

An access road from Little Tujunga Canyon Road to the Reservoir will be restored.

## PHASE 1: SEDIMENT REMOVAL BEGINS

- Up to 1.5 million cubic yards of sediment will be removed over the course of 5 years or less.
- There will be controlled releases of water into Pacoima Wash, before the sediment is then excavated and trucked to nearby landfills or gravel pits.

SPRING  
2026



TENTATIVELY  
2030



## PHASE 2: CONSTRUCTION BEGINS

- An additional 2.2- 4 million cubic yards of sediment will be removed over the course of 10 years or less.
- Sediment will be moved by either trucks and/or a conveyor belt system.

## PHASE 3: LONG TERM MAINTENANCE

A long-term maintenance plan will be implemented in order to reduce the need for further large-scale sediment-removal projects such as this one.

**\*Note: These dates are all subject to change**